



GENERAL NOTES

- ALL EXISTING MARLITE ON SALES FLOOR IS TO BE REMOVED & REPLACED WITH NEW PER FINISH SCHEDULE A6.01. EXISTING MARLITE IN NON-CUSTOMER-FACING OFFICES TO REMAIN.
- WOOD TRIM AT TOP OF MARLITE IS TO BE REMOVED, UNLESS NOTED OTHERWISE.
- ALL WOOD TRIM AROUND OPENINGS OR DOORS IS TO BE REMOVED, UNLESS NOTED OTHERWISE.
- ALL SHELVING & COUNTER DIMENSIONS ARE TO BE FIELD VERIFIED.
- THE GENERAL CONTRACTOR SHALL SUPPLY & INSTALL A-24 X 5'-6" LONG WOOD COAT RACK WITH TEN (10) COAT HOOKS. PAINT WOOD P-15(B). SEE FINISH SCHEDULE ON SHEET A6.01. MOUNT AT 5'-0" ABOVE FINISHED FLOOR. COORDINATE WITH FOOD LION CONSTRUCTION MANAGER.

PRE-FAB CABINETS

CAB-1	BSB CABINET-LYONS-MODEL 5356(FRONT); JOHN BOOS-MODEL RDRS3628-FL (BACK)	EXISTING
CAB-2	T&A CABINET-LYONS-MODEL R435	NEW
CAB-3	WORK ROOM CABINET-ROYSTON-MODEL 60082334-153	NEW
CAB-4	CUSTOMER SERVICE KIOSK 8'-LYONS-MODEL S728	NEW

LOUNGE EQUIPMENT

LE-1	REFRIGERATOR-FRIGIDAIRE-MODEL #33E892	NEW
LE-2	MICROWAVE	RELOCATED
LE-3	COFFEE MAKER-TOUCH ESSENTIALS-MODEL #T214B	NEW
LE-4	S.S. TABLE-JOHN BOOS & CO.-MODEL #S16R5-2436SSW	NEW