

FINISH SCHEDULE								
ROOM NO.	ROOM NAME	FLOOR	BASE	WALLS		CEILING	CEILING HEIGHT	SCHEDULE NOTES
				MATERIAL	FINISH			
100A	EXISTING AIRLOCK #1	NEW CPT-1	---	EXISTING TO REMAIN BRICK & GWB	PAINT GWB P-7 (A)	EXISTING TO REMAIN GWB PAINT P-4 (D)	12'-11"±	13
100B	EXISTING AIRLOCK #2	NEW CPT-1	---	EXISTING TO REMAIN BRICK & GWB	PAINT GWB P-7 (A)	EXISTING TO REMAIN GWB PAINT P-4 (D)	12'-11"±	13
101	EXISTING VESTIBULE	NEW CPT-1	NEW VB-1	EXISTING TO REMAIN BRICK & GWB / NEW GWB & WALL COVERING	PAINT GWB P-7 (A) / NEW WP-7	EXISTING TO REMAIN GWB PAINT P-4 (D)	12'-11"±	3, 13
102	REMODELED SALES AREA	NEW VCT-1	NEW VB-1	EXISTING TO REMAIN & NEW GWB / NEW WALL COVERING	NEW WP-7 & P-7 (A) / NEW DECORATIVE ACCENT BAND P-13 (A)	EXISTING TO REMAIN ACT / NEW ACT TO MATCH EXISTING	12'-11"±	3, 7, 13, 15, 16, 17, 19
103	REMODELED WORK ROOM	NEW VCT-1	NEW VB-1	EXISTING TO REMAIN & NEW GWB / NEW WP	NEW WP-6 AT WALLS WITHOUT COUNTER & SHELVES OR DOOR & SAFE / PAINT GWB P-7 (A)	EXISTING TO REMAIN ACT / NEW ACT TO MATCH EXISTING	12'-0"±	1, 3, 5, 7, 13, 15, 16
104	EXISTING WORK ROOM CLOSET	EXISTING TO REMAIN VCT	EXISTING TO REMAIN VB	EXISTING TO REMAIN GWB	---	EXISTING TO REMAIN GWB	12'-1"±	7, 13
105	EXISTING RISER ROOM	EXISTING TO REMAIN CS	---	EXISTING TO REMAIN GWB / CMU	---	EXISTING TO REMAIN GWB	---	.
106	REMODELED CORRIDOR	NEW VCT-1	NEW VB-1	NEW WP	NEW WP-6 UP TO 6" ABOVE ACOUSTICAL TILE CEILING	EXISTING TO REMAIN ACT / NEW ACT TO MATCH EXISTING	8'-9"±	1, 7, 13
107	REMODELED MEN'S RESTROOM	EXISTING TO REMAIN QT	EXISTING TO REMAIN QTB	EXISTING TO REMAIN CWT	EXISTING TO REMAIN CWT	EXISTING TO REMAIN GWB PAINT P-4 (A)	7'-11"±	6, 7, 9, 13
108	REMODELED WOMEN'S RESTROOM	EXISTING TO REMAIN QT	EXISTING TO REMAIN QTB	EXISTING TO REMAIN CWT	EXISTING TO REMAIN CWT	EXISTING TO REMAIN GWB PAINT P-4 (A)	7'-11"±	6, 7, 9, 13
109	EXISTING GROCERY STAGING / RECEIVING	EXISTING TO REMAIN CS	---	EXISTING TO REMAIN CMU	---	EXISTING TO REMAIN EXPOSED STRUCTURE	---	2, 4, 7, 14
110	REMODELED LOUNGE	EXISTING TO REMAIN VCT	NEW VB-1	NEW WP	NEW WP-6	EXISTING TO REMAIN ACT	7'-11"±	1, 7, 13
111	EXISTING JANITOR'S ROOM	EXISTING TO REMAIN CS	---	EXISTING TO REMAIN CMU	PAINT CMU P-4 (C)	EXISTING TO REMAIN GWB PAINT P-4 (C)	7'-11"±	7, 13
112	EXISTING MECHANICAL ROOM	EXISTING TO REMAIN CS	---	EXISTING TO REMAIN CMU & GWB	---	EXISTING TO REMAIN EXPOSED STRUCTURE	---	13
113	EXISTING MEAT PREP	EXISTING TO REMAIN QT	EXISTING TO REMAIN QTB	NEW / EXISTING TO REMAIN FRP	NEW WP-5 / EXISTING TO REMAIN FRP	EXISTING TO REMAIN INSULATED PRE-FAB PANELS	10'-0"±	1, 7, 13
114	EXISTING MEAT OFFICE	EXISTING TO REMAIN QT	EXISTING TO REMAIN QTB	EXISTING TO REMAIN CMU & INSULATED PRE-FAB PANELS	PAINT CMU & INSULATED PRE-FAB PANELS P-4 (C)	EXISTING TO REMAIN PLYWOOD PAINT P-4 (B)	7'-11"±	7, 13
115	NEW DMO / ASSOCIATES TRAINING ROOM	NEW VCT-1	NEW VB-1	NEW WP	NEW WP-6	NEW ACT-1	8'-0"	1, 5, 7, 13
116	EXISTING PRODUCE PREP	NEW CS	EXISTING TO REMAIN VB / PAINT EXISTING TO REMAIN WD. P-4 (B)	EXISTING TO REMAIN CMU & FRP	PAINT EXISTING CMU P-4 (C)	EXISTING TO REMAIN ACT	9'-11"±	2, 7, 13
117	REMODELED DELI / BAKERY PREP	EXISTING TO REMAIN QT	EXISTING TO REMAIN QTB	EXISTING TO REMAIN CWT / NEW CWT ACCENT BAND	NEW CERAMIC TILE CWT-1 (G8) AT ACCENT BAND ONLY	EXISTING TO REMAIN ACT	8'-6"±	6, 12, 13
118	REMODELED DELI / BAKERY CLOSET	EXISTING TO REMAIN QT	EXISTING TO REMAIN QTB	EXISTING TO REMAIN FRP	---	EXISTING TO REMAIN PLYWOOD PAINT P-4 (B)	7'-9"±	7, 13

FINISH SCHEDULE NOTES:

1. MARLITE BRAND PANELS (MBP): USE TRADITIONAL PROFILE ALUMINUM TRIM PIECES WITH A FACTORY FINISH TO MATCH MARLITE. INSTALL REPLACEMENT MARLITE BRAND PANELS PER MANUFACTURER'S SPECIFICATIONS. USE ONLY ACCEPTABLE MARLITE ACCESSORIES.

→ EXISTING MARLITE PANELING (WP-3) TO REMAIN AND REPAIR AS NEEDED WITH MATCHING PANELS.

→ EXISTING MARLITE PANELING TO BE REPAIRED AS NEEDED, THEN PAINTED P-2(G) - REFER TO SPECIFICATIONS ON PROPER PRIMER, REPAIR & COATING INSTRUCTIONS.

• SEE FINISH MATERIAL/COLOR LEGEND FOR NEW MARLITE BRAND PANELS (WP-6).
2. CAULK 2x6 P.T. WOOD BASEBOARD AT COOLER/FREEZER PANELS & METAL STUD WALLS IN REAR AREA, TOP AND BOTTOM. PAINTED WITH P-4(B).

3. ALL GYPSUM WALLBOARD TO BE TAPED, MUDDED AND SANDED (PAINT READY).

4. GENERAL CONTRACTOR SHALL PAINT FIRE LANES IN REAR AREAS, IF REQUIRED.

5. NEW MILLWORK LAMINATE TO BE WILSONART #4842-60 "CANYON ZEPHYR" MATTE FINISH, REFER TO A4.06, PAINT SUPPORTS P-15(B). NEW LAMINATE IN NON-CUSTOMER-FACING OFFICES TO BE FORMICA #889-68 "DESERT BEIGE" MATTE FINISH, REFER TO A4.06, PAINT SUPPORTS P-15(B).

6. REFER TO A2.02 AND A4.03 FOR DELI/BAKERY AND RESTROOM TILE.

7. DOORS AND FRAMES TO BE PAINTED- P-15(B), UNLESS OTHERWISE NOTED. (EXCEPT ALUM. STOREFRONT DOORS & WINDOWS). SEE SHEET A6.02 FOR FINISHES.

8. ALL WOOD TRIM ADJACENT TO OR CASINGS AROUND DOORS, WINDOWS, TOP OF MARLITE OPENINGS TO BE REMOVED.

9. ALL WOOD TRIM AT CEILINGS, TO BE PAINTED P-7(B).

10. RESINOUS DECORATIVE FLOORING SHALL BE PURCHASED FROM DURA-FLEX INC. (CONTACT: KEVIN STEPHENS 919-208-8662), OR PROTECTIVE INDUSTRIAL POLYMERS (CONTACT: STEVE MCCAMEY AT 804-937-0600).

11. PROVIDE 1/2" GYP. BD. OVERLAY ON EXISTING CEILING FINISH TAPE, MUD, SAND AND PREP FOR NEW PAINT AS INDICATED. TEMPORARILY UNINSTALL EXISTING LIGHT FIXTURE AS REQUIRED TO INSTALL OVERLAY.

12. PRE-FAB COOLER/FREEZER PANELS AND DOORS TO BE PAINTED P-2(E), COORDINATE PAINT METHOD W/FOOD LION CONSTRUCTION MANAGER.

13. COORDINATE WITH FOOD LION CONSTRUCTION MANAGER FOR PAINTING OF WALLS, DOORS & FRAMES.

14. PROVIDE 4" HIGH FIRE RETARDANT (FRT) PLYWOOD WITH FRT 2x6 WOOD BASE @ EXPOSED COOLER/FREEZER WALLS - PAINT BASE PER NOTE #2 AND LEAVE PLYWOOD UNFINISHED.

15. ALL WALLS BELOW 8' WITHOUT WALL PANELING SHALL BE PAINTED WITH P-7(A), EXCEPT THE SALES FLOOR WILL RECEIVE NEW WALL COVERING (SEE A2.02).

16. SAFE AND SAFE TRIM TO BE PAINTED P-2(B) ON SALES AREA SIDE AND P-15(B) ON WORK ROOM SIDE. (HAND MACHINE ROLLED NOT BRUSHED).

17. ALL SALES FLOOR GWB WALLS TO RECEIVE SHERWIN WILLIAMS PROBLOCK OIL BASED PRIMER PRIOR TO PAINTING - SALES FLOOR ONLY.

18. REMOVE 2x6 WOOD BASE, APPLY RESINOUS FLOORING DIRECTLY TO CMU, FRP, AND COOLER WALLS. RESINOUS COVE BASE TO MATCH HEIGHT OF REMOVED WOOD BASE.

19. SALES AREA COLUMNS TO BE SANDED, PRIMED & PAINTED P-7(B) EPOXY. DO NOT PAINT STAINLESS STEEL WRAPS.

20. CONFERENCE ROOM CARPET TO VCT TRANSITION STRIP TO BE ARMSTRONG-VT-060 (BLACK).
- GENERAL FINISH NOTES:
1. ALL CONSTRUCTION TO BE TYPE IIB OR BETTER (2012 IBC).

2. REFER TO SHEET A1.04 FOR ADDITIONAL CEILING INFORMATION.

3. REFER TO A1.05 FOR ADDITIONAL FLOORING INFORMATION.

4. REFER TO SHEET A2.02 FOR SALES FINISHES & A4.03 FOR RESTROOM FINISHES.

5. REFER TO SHEET A4.04 FOR VESTIBULE FINISHES.

6. REFER TO G1.01 FOR NATIONAL ACCOUNT INFORMATION.

7. DO NOT PAINT STAINLESS STEEL / ALUMINUM TRIM.

8. REFER TO SPEC BOOK FOR PAINT SPECS & FINISH INFORMATION.

9. COORDINATE WITH FOOD LION CONSTRUCTION SUPERVISOR FOR PAINTING OF WALLS, DOORS & FRAMES.
- | COOLER / FREEZER FINISH SCHEDULE | | | | | |
|----------------------------------|--------------------------------|--------------|---|------------------------|-------|
| MARK | NAME | SIZE (SQFT.) | FLOOR | BASE | NOTES |
| A | EXISTING DAIRY COOLER | 480 | EXISTING TO REMAIN CS | --- | . |
| B | EXISTING ICE CREAM FREEZER | 149 | EXISTING TO REMAIN INSULATED
PANEL FLOOR | --- | . |
| C | EXISTING STORAGE FREEZER | 32 | EXISTING TO REMAIN INSULATED
PANEL FLOOR | --- | . |
| D | EXISTING MEAT COOLER | 245 | EXISTING TO REMAIN QT | EXISTING TO REMAIN QTB | . |
| E | EXISTING MEAT FREEZER | 149 | EXISTING TO REMAIN INSULATED
PANEL FLOOR | --- | . |
| F | EXISTING PRODUCE COOLER | 265 | EXISTING TO REMAIN CS | --- | . |
| G | EXISTING DELI / BAKERY FREEZER | 195 | EXISTING TO REMAIN INSULATED
PANEL FLOOR | --- | 1 |
| H | EXISTING DELI / BAKERY COOLER | 72 | EXISTING TO REMAIN QT | EXISTING TO REMAIN QTB | 1 |
- COOLER / FREEZER FINISH SCHEDULE NOTES:
1. ELECTROSTATICALLY PAINTED COOLER & FREEZER DOORS [P-2 (E)] TO BE PAINTED BY CASE PAINTER.
- FINISH MATERIAL/COLOR LEGEND:
- FLOORS: (SEE SHEETS A1.05 & A4.02 FOR SPECIFIC MATERIALS)

R-1

RESINOUS TOPPING - COLOR FOOD LION #FL105. SEE FINISH SCHEDULE NOTE #10.

R-2

RESINOUS TOPPING - COLOR FOOD LION #FL106. SEE FINISH SCHEDULE NOTE #10.

CPT-1

CARPET-PORTRICO DIPLOMAT "MINK"

CPT-2

CARPET TILE-MOHAWK BT417 RESTORE "EMERGE" #358"

CPT-3

CARPET-OAK CHARCOAL #4307

CS

CONCRETE SEALER

QT

QUARRY TILE

PT-1

DAL TILE - REMINISCENT SERIES "RECLAIMED GRAY" #RM23 UNPOLISHED 12"x12" FLOOR TILE (SEE G9 FOR GROUT DETAILS)

CT

DAL TILE - HEATHLAND SERIES, "AMBER HL03" 12"x12" GLAZED CERAMIC FLOOR TILE (SEE G10 FOR GROUT DETAILS)

VCT-1

VINYL COMPOSITION TILE - ARMSTRONG RAFIA-COCOA 55805 12"x24"

VCT-2

VINYL COMPOSITION TILE - EXCELOX IMPERIAL TEXTURE "EARTHSTONE GREIGE" 12"x12"

VCT-3

VINYL COMPOSITION TILE - EXCELOX IMPERIAL TEXTURE "ANTIQUE WHITE" 12"x12"

WM

WALK-OFF MAT-PORTRICO SYSTEMS "DIPLOMAT"

MTP

METAL TREAD PLATE

BASE:

R-1

RESINOUS TOPPING, FL105, TURNED UP WALL. SEE SHT. A3.02.

R-2

RESINOUS TOPPING, FL106, TURNED UP WALL. SEE SHT. A3.02.

QTB

QUARRY TILE BASE

PB-1

DAL TILE - REMINISCENT SERIES, "MOMENTO WHITE" #RM20 UNPOLISHED 6"x12" (SEE G8 FOR GROUT DETAILS). 12"x12" TILE CUT IN FIELD TO CREATE 6"x12"

CIB

DAL TILE - AFFINITY SERIES, "BEIGE AF02" P-43C9 3"x12" (SEE G7 FOR GROUT DETAILS).

VB-1

4"H COVE BASE, JOHNSONITE MATTE BLACK #40

MTPB

METAL TREAD PLATE BASE

MCBB

MCQUE BOX RAIL

WD

2x6 P.T. WOOD

CEILING FINISHES:

ACT-1

2x4 ARMSTRONG HUMAGUARD PLUS IN PRELUDE XL GRID

ACT-2

2x4 2" FOAM DOUBLE SIDED FIBERLITE FRP PANEL BY NUDO PRODUCTS

ACT-3

2x4 ARMSTRONG VINYL CLAD TILE IN PRELUDE XL GRID

FRP

FIBER REINFORCED PANEL

GB

PAINTED GYPSUM BOARD

TRIM:

ST-1

SCHLUTER - DILEX-EHK EBHKU11-011 STAINLESS STEEL COVE BASE

ST-2

SCHLUTER - RONDEC R0100E STAINLESS STEEL TRIM

CR-1

ACROVYN 4000 FR-225N ACCENT RAIL (BLACK) #108

PLASTIC LAMINATE:

PL-1

WILSONART "CANYON ZEPHYR" #4842-60 MATTE FINISH

PL-2

FORMICA "DESERT BEIGE" MATTE FINISH

WALLS SURFACES:

WP-1

WALL PANEL - "WHEAT" #5347-S4 MARLITE PANEL

WP-2

WALL PANEL - "CODY" #194 MARLITE PANEL

WP-3

WALL PANEL - "LAREDO OAK" #324-S2 MARLITE PANEL

WP-4

WALL PANEL - "PLANTATION OAK" #323-S2 MARLITE PANEL

WP-5

WALL PANEL - "PAINTABLE WHITE" #1001-BG2 MARLITE PANEL

WP-6

WALL PANEL - "MORNING HAZE" #5446-S2 MARLITE PANEL

WP-7

WALL COVERING - PEARL GRAY #136, .040" ACROVYN

WP-8

NOT USED

WP-9

FRP - "WHITE" P-100 MARLITE

WP-10

FRP - "ALMOND" P-118 MARLITE

CWT-1

DAL TILE "DESERT GRAY" X114 4"x4" SEE (G2) FOR GROUT DETAILS

CWT-2

DAL TILE "ARCTIC WHITE" 0190 6"x6" SEE (G3) FOR GROUT DETAILS

CWT-3

DAL TILE-AFFINITY SERIES "BEIGE AF02" 10x14" SEE (G7) FOR GROUT DETAILS

CWT-4

DAL TILE-BRITTON SERIES "MUSHROOM" BX03 9"x12" (MATCH EXISTING GROUT)

CWT-5

DAL TILE- "URBAN PUTTY" 0161 SEMI-GLOSS 4"x12" SEE G7 FOR GROUT DETAILS

CWT-6

DAL TILE- "URBAN PUTTY" 0161 MATTE 4"x12" SEE G7 FOR GROUT DETAILS

CWT-7

DAL TILE- "ARCHITECTURAL GRAY" 0109 SEMI-GLOSS 6"x6" SEE G7 FOR GROUT DETAILS

CWT-8

DAL TILE- "ARTISAN BROWN" 0144 SEMI-GLOSS 1"x6" SEE G7 FOR GROUT DETAILS

PWT-1

DAL TILE REMINISCENT SERIES "MOMENTO WHITE" #RM20 UNPOLISHED 12"x12" WALL TILE SEE (G8) FOR GROUT DETAILS

PAIN:

P-1

COLOR: SW 6141 "SOFTER TAN"

P-2

COLOR: SW 7650 ELLIE GRAY

P-3

COLOR: SW 6142 "MACADAMIA"

P-4

COLOR: SW 7005 "PURE WHITE"

P-5

COLOR: SW 6732 "ORGANIC GREEN"

P-6

COLOR: SW 7068 "GRIZZLE GRAY"

P-7

COLOR: SW 7001 "MARSHMALLOW"

P-8

COLOR: "HIGH TRAFFIC WHITE"

P-9

COLOR: SW 6071 "POPULAR GRAY"

P-10

COLOR: SW 7038 "TONY TAUPE"

P-11

COLOR: SW 7055 "ENDURING BRONZE"

P-12

COLOR: "TRAFFIC YELLOW"

P-13

COLOR: SW 6227 "MEDITATIVE"

P-14

COLOR: SW 6992 "INKWELL"

P-15

COLOR: SW 7031 "MEGA GREIGE"

P-16

COLOR: SW 7030 "ANEW GRAY"

P-17

COLOR: SW 7562 "ROMAN COLUMN"

P-18

COLOR: SW 9087 "SMOKY BEIGE"

INTERIOR GROUT FINISH LEGEND:

(G1)

TO USE GROUT: CUSTOM BUILDING PRODUCTS "TRUFFLE" #540

(G2)

TO USE GROUT: CUSTOM BUILDING PRODUCTS "OYSTER GRAY" #386

(G3)

TO USE GROUT: CUSTOM BUILDING PRODUCTS "NEW TAUPE" #185

(G4)

TO USE GROUT: CUSTOM BUILDING PRODUCTS "BONE" #382

(G5)

TO USE GROUT: CUSTOM BUILDING PRODUCTS "OYSTER" #381

(G6)

TO USE GROUT: CUSTOM BUILDING PRODUCTS "NATURAL" #09

(G7)

TO USE GROUT: CUSTOM BUILDING PRODUCTS "LINEN" #122

(G8)

TO USE GROUT: CUSTOM BUILDING PRODUCTS "CAPE GRAY" #546

(G9)

TO USE GROUT: CUSTOM BUILDING PRODUCTS "WINTER GRAY" #355

(G10)

TO USE GROUT: CUSTOM BUILDING PRODUCTS "SAHARA TAN" #22

NOTE: USE A 1/16" JOINT FOR CERAMIC TILE. USE A 3/16" JOINT FOR PORCELAIN TILE. ALL FLOOR TILE GROUT SHALL BE CEG-IG 100% SOLIDS INDUSTRIAL GRADE EPOXY GROUT BY CUSTOM BUILDING PRODUCTS (COLOR AS INDICATED IN DRAWINGS).

INTERIOR WALL FINISH PAINTING LEGEND:

(A)

EG-SHEL

(B)

SEMI-GLOSS

(C)

LOW-GLOSS

(D)

FLAT

(E)

ELECTROSTATIC

REVISIONS

NO.	DESCRIPTION	DATE
-----	-------------	------

FOOD LION 2560

7514 NORTH POINT ROAD
EDGEMERE, MD

FINISH SCHEDULE

DRAWING FILE NAME

2560A6.01_00

RFS JOB #

2019-042

DATE

02/21/20

A6.01

20 OF 21